BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/09/2018-19 Dated: 27-2-2019

APPROVED TENDER SCHEDULE –'B'

Item-66

Name of Work:-Providing and fixing play equipments to parks in ward no 04, Yelahanka Division

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri C R Aravind Kumar	
				Rate	Rate in Words
1	Providing and fixing FRP slide of width 2ft length 9ft and hiight 5 ft with a platform of 2ft x 2ft aluminium chequered plate steps made out of GI Sheet 4" with thread metalic and powedered coated including fixing the play equipments in CC 1:2:4 curing etc complete with all lead and lift loading unloading and any other incidental charges and as per the drawing and specification and direction of the engineer incharge of the work.	Each	1.00	34320.00	Rupees Thirty Four Thousand Three Hundred Twenty Only
2	Providing children play standard duck wheel equipment: this is a macro revolver made up of an 4feet diameter platform with 1.5 mm thick aluminium chequered plate supported well at the bottom. There is a 100mm dia MS pipe at the center with two Nos of ball bearings 2 Nos LDPE ducks and 1No of plastic sheet flat seats. all	Each	1.00	39600.00	Rupees Thirty Nine Thousand Six Hundred Only
3	Childrens Play Thriller: this children play thriller comprasing 4 platforms with chequred platforms of size 3ft x 3 ft and top covered with serrated moulded plastic canopies. the three platforms are 5ft height and one platform of 3ft height one perforted tunnel one swinging bridge and one arch bridge inter connects the platforms the four platforms should be attached with steps made out of GI sheet 4" thick spiral slide with additional platform roller slide with plastic rolls loop rings one FRP slide. Roman links and double swing with rubber coating the 3ft height platform to be fitted with doubled duck swing FRP dual kids slid and steps made of GI sheets all pipes are of 14 guage MS pipe with ISI Marking all the parts are to powdered coated with UV stabilised make powder	Each	1.00	591360.00	Rupees Five Lakh Ninety One Thousand Three Hundred Sixty Only
4	Providing and fixing MINI MULTI PLAY SYSTEM consisting if LDPE tube slide of 7ft sliding length and 26" dia and LDPE crawl tube of 6ft crawling length , a chain ladder firement etc ncluding fixing the play equipments in CC 1:2:4 curing etc complete with all lead and lift loading unloading and any other incidental charges and as per the drawing	Each	2.00	248160.00	Rupees Two Lakh Forty Eight Thousand One Hundred Sixty Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri C R Aravind Kumar	
				Rate	Rate in Words
5	Providing Children Play Platform Equipments this multi play system comprises of two platforms with serrated moulded FRP canopies etc ncluding fixing the play equipments in CC 1:2:4 curing etc complete with all lead and lift loading unloading and any other incidental charges and as per the drawing and specification and direction of the engineer incharge of the work	Each	1.00	462000.00	Rupees Four Lakh Sixty Two Thousand Only
6	Providing Children Play Standard Slide Equipment: Made out of MS A' Class pipes main frame are in 25mm and other railings are in 20mm 1.5 mtrs h x 3.00 meters long x .45 mtrs width sliding surface fitted with SS Sheet. etc ncluding fixing the play equipments in CC 1:2:4 curing etc complete with all lead and lift loading unloading and any other incidental charges and as per the drawing and specification and direction of the engineer incharge of the work.	Each	2.00	24640.00	Rupees Twenty Four Thousand Six Hundred Forty Only
7	Providing Children Play Merry Go Round Equipments : Made of M S A class pipes main pillers are in 100mm fitted with shaft and two bearning and other cross members are in 25 & 20mm MA "A class piples bottom ring is made out of 25m and righ size is 1.20 mtrs dia fitted with four seats are in metntal sats of 250 x 200 x 18 SGE etc ncluding fixing the play equipments in CC 1:2:4 curing etc complete with all lead and lift loading unloading and any other incidental charges and as per the drawing and specification and direction of the engineer incharge of the work.	Each	2.00	27104.00	Rupees Twenty Seven Thousand One Hundred Four Only
8	Providing Children play main wheel equipments : Made of MS A Class pipes main pillers are in 100mm dia fitted with shaft and two bearing and other cross members are in 25 & 20 mm MS A Class pipees the bottom ring is made out of 32mm NB pipes and 1.20 mtrs dia etc ncluding fixing the play equipments in CC 1:2:4 curing etc complete with all lead and lift loading unloading and any other incidental charges and as per the drawing and specification and direction of the engineer incharge of the work.	Each	2.00	21824.00	Rupees Twenty One Thousand Eight Hundred Twenty Four Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri C R Aravind Kumar	
				Rate	Rate in Words
9	Providing children play two seater swing duck Equipments : this swing consist of 2 Nos FRP Ducks supported by MS chains of length 1.05 mtrs each duck is suspended by 3 lines of chains. The chains are supported by circular housings with bearing from which the chain in suspended. etc ncluding fixing the play equipments in CC 1:2:4 curing etc complete with all lead and lift loading unloading and any other incidental charges and as per the drawing and specification and direction of the engineer incharge of the work.	Each	2.00	39600.0	Rupees Thirty Nine Thousand Six Hundred Only
10	Providing Children Play standard Spring Duck Equipment : The system consistes of an FRP coloured duck rocking on 10mm dia heavy duty colled spring etc ncluding fixing the play equipments in CC 1:2:4 curing etc complete with all lead and lift loading unloading and any other incidental charges and as per the drawing and specification and direction of the engineer incharge of the work.	Each	3.00	11000.00	Rupees Eleven Thousand Only
11	Providing Children Play Standard see saw seater equipment : This equipments is made up of main beam 50mm MS pipe A class of lenght 1.98mtr with two handles welded at the ends as a hand are made of 20mm A class pipe the main beam is pivoted to the bottom supported etc ncluding fixing the play equipments in CC 1:2:4 curing etc complete with all lead and lift loading unloading and any other incidental charges and as per the drawing and specification and direction of the engineer incharge of the work.	Each	1.00	15664.00	Rupees Fifteen Thousand Six Hundred Sixty Four Only
12	Providing Children Play Two seater standard swing Equipment : This swing consist of 2 Nos seats of solid metal seats powder coated of size 500mm x 250mm x 16 SWG supported by MS chains of length 1.8 mtrs each seat is suspended by 1 line of chain. the chains are supported by circular housings with bearing from which the chain in suspended. etc ncluding fixing the play equipments in CC 1:2:4 curing etc complete with all lead and lift loading unloading and any other incidental charges and as per the drawing and specification and direction of the engineer incharge of the work.	Each	1.00	21120.00	Rupees Twenty One Thousand One Hundred Twenty Only
13	Sand bed Sl No 54, code 0772 page III SR 2018-19	Cum	30.00	1479.00	Rupees One Thousand Four Hundred Seventy Nine Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.